



CHINO DESALTER PHASE 3

Comprehensive Predesign Report



Prepared for

**Jurupa Community Services District,
City of Ontario, and
Western Municipal Water District**

REVISED FINAL

December 2010



Jurupa Community Services District, City of Ontario, and
Western Municipal Water District

**CHINO DESALTER PHASE 3
COMPREHENSIVE PREDESIGN REPORT**

TABLE OF CONTENTS

Page No.

EXECUTIVE SUMMARY

SECTION 1 - INTRODUCTION

1.1	BACKGROUND	1-1
	1.1.1 Phase 3 Project.....	1-1
	1.1.2 Project Sponsors.....	1-1
1.2	OBJECTIVES.....	1-2
1.3	AUTHORIZATION.....	1-6
1.4	ABBREVIATIONS.....	1-7
1.5	REFERENCES.....	1-9

SECTION 2 - GROUNDWATER AND WELLS

2.1	INTRODUCTION	2-1
2.2	HYDRAULIC CONTROL.....	2-1
	2.2.1 Chino Creek Well Field (CCWF)	2-2
2.3	CHINO DESALTER WELL FIELDS	2-2
	2.3.1 Models.....	2-5
	2.3.1.1 GEOSCIENCE Groundwater Model.....	2-5
	2.3.1.2 Wildermuth Model.....	2-9
	2.3.1.3 Conclusions from Groundwater Models	2-12
2.4	NEW WELL FACILITIES	2-15
	2.4.1 Well Construction Standards and Criteria	2-15
	2.4.1.1 Pump and Driver.....	2-15
	2.4.1.2 Wellhead Piping and Appurtenances.....	2-16
	2.4.1.3 Surge Control.....	2-17
	2.4.1.4 Electrical Equipment.....	2-18
	2.4.1.5 Instrumentation and Control	2-19
	2.4.1.6 Site Work	2-20

SECTION 3 - RAW WATER PIPELINES

3.1	INTRODUCTION	3-1
3.2	CHINO CREEK WELL FIELD PIPELINES.....	3-1
3.3	CHINO II WELL FIELD EXPANSION PIPELINE.....	3-3
3.4	CHINO I/II RAW WATER INTERTIE.....	3-5
	3.4.1 Water Quality	3-11
3.5	RAW WATER PIPELINE CRITERIA.....	3-14

SECTION 4 - CHINO DESALTERS

4.1	INTRODUCTION	4-1
4.2	WATER QUALITY	4-1
4.2.1	Sources	4-2
4.2.2	Nitrate	4-2
4.2.5	VOC Modeling	4-8
4.2.6	VOC Treatment Recommendations	4-11
4.2.6.1	TCE Treatment Recommendations	4-11
4.2.6.2	TCP Treatment Recommendations	4-15
4.2.7	Other Water Quality Contaminants	4-18
4.3	CHINO I DESALTER	4-20
4.3.1	Existing Process Facilities	4-20
4.3.2	Process Facility Modifications	4-26
4.3.3	Cost Allocations	4-30
4.4	CHINO II DESALTER	4-31
4.4.1	Existing Process Facilities	4-31
4.4.2	Process Facility Modifications	4-35
4.4.3	Cost Allocations	4-35
4.4.3.1	Costs Shared by Sponsors Only	4-35
4.4.3.2	Costs Shared by All CDA Members	4-37
4.4.3.3	Costs Shared by Sponsors and All CDA Members	4-37

SECTION 5 - CONCENTRATE DISPOSAL FACILITIES

5.1	BACKGROUND	5-1
5.2	CHINO I SARI CAPACITY	5-2
5.3	CHINO II SARI CAPACITY	5-4
5.4	CONCENTRATE REDUCTION OPTIONS	5-8

SECTION 6 - PRODUCT WATER FACILITIES

6.1	OVERVIEW	6-1
6.1.1	Deliveries to JCSD	6-3
6.1.2	Deliveries to Ontario	6-3
6.1.3	Deliveries to WMWD	6-9
6.2	PRODUCT WATER PIPELINES	6-11
6.2.1	Chino II to Riverside-Hamner and Arlington Pipelines	6-12
6.3	PUMP STATIONS	6-16
6.3.1	Chino II Product Water Pump Stations	6-16
6.3.1.1	Chino II 1010 Zone Pump Station	6-19
6.3.2	Milliken Pump Station	6-22
6.3.3	Surge Protection	6-24
6.3.3.1	Chino II 1010 Zone Product Water Pumping Station Surge Analysis	6-24
6.4	CHINO I – CHINO II PRODUCT WATER INTERTIE	6-24
6.4.1	Operational Intertie Practices	6-24
6.4.2	Physical Intertie Options	6-25

SECTION 7 - PERMITS

7.1	INTRODUCTION	7-1
7.2	CALIFORNIA ENVIRONMENTAL QUALITY ACT (CEQA)	7-1
7.3	CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)	7-1
7.4	SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (AQMD)	7-2
7.5	CALIFORNIA DEPARTMENT OF TRANSPORTATION (CALTRANS)	7-2
7.6	CALIFORNIA DIVISION OF OCCUPATIONAL SAFETY AND HEALTH (CAL/OSHA)	7-2
7.7	ARMY CORPS OF ENGINEERS (ACE)	7-2
7.8	CALIFORNIA DEPARTMENT OF FISH AND GAME (DFG)	7-3
7.9	CALIFORNIA WATER RESOURCES CONTROL BOARD (STATE WATER BOARD)	7-3
7.10	SAN BERNARDINO COUNTY	7-4
	7.10.1 Building Permit	7-4
	7.10.2 Fire Permit	7-4
	7.10.3 Well Drilling Permit	7-4
	7.10.4 Encroachment Permit	7-4
	7.10.5 Flood Control Permit	7-4
7.11	RIVERSIDE COUNTY	7-4
	7.11.1 Building Permit	7-5
	7.11.2 Fire Permits	7-5
	7.11.3 Well Drilling Permit	7-5
	7.11.4 Encroachment Permit	7-5
	7.11.5 Flood Control Permit	7-5
7.12	CITY OF CHINO	7-6
	7.12.1 Building Permit	7-6
	7.12.2 Fire Permits	7-6
	7.12.3 Encroachment Permit	7-6
	7.12.4 Storm Drain Discharge	7-6
7.13	CITY OF ONTARIO	7-6
	7.13.1 Building Permit	7-7
	7.13.2 Fire Permits	7-7
	7.13.3 Encroachment Permit	7-7
7.14	CITY OF NORCO	7-7
	7.14.1 Encroachment Permit	7-7
7.15	SOUTHERN CALIFORNIA EDISON (SCE)	7-7
7.16	INLAND EMPIRE UTILITIES AGENCY (IEUA)	7-8
7.17	UNION PACIFIC RAILROAD (UPRR)	7-8
7.18	FEDERAL COMMUNICATIONS COMMISSION (FCC)	7-8
7.19	FEDERAL AVIATION ADMINISTRATION (FAA)	7-8

SECTION 8 - COST ESTIMATES

8.1	INTRODUCTION	8-1
8.2	SARI COSTS	8-1
8.3	CAPITAL COSTS	8-4
	8.3.1 Option A—Expand Chino II to 20.5 mgd and Modify Chino I to Nameplate Capacity	8-4
	8.3.2 Option B—Expand Chino II to 22.7 mgd (Including Raw Water Bypass)	8-6
	8.3.3 Option C—Expand Chino II to 22.7 mgd (Including Concentrate Reduction Facilities)	8-7
	8.3.4 Cost Estimates	8-11

8.4	OPERATIONS AND MAINTENANCE COSTS.....	8-11
8.4.1	Pipeline O&M Costs.....	8-13
8.4.2	Well and Pump Station O&M Costs.....	8-13
8.4.3	Treatment Plant O&M Costs.....	8-14
8.5	FUNDING AND COST OFFSETS	8-17
8.5.1	Grant Funding	8-17
8.5.2	MWD LRP Funding.....	8-17
8.5.3	Groundwater Replenishment.....	8-18
8.6	SUMMARY OF COSTS	8-18

APPENDICES

APPENDIX A: WELL FIELD

- Appendix A.1: Letter from Chino Basin Watermaster (8 July, 2009 & 13 October, 2009)
- Appendix A.2: Tabulation of Chino Well Field Modeling Data (GEOSCIENCE, 2008)
- Appendix A.3: Chino Desalter Wells Historical and Modeled Levels and Pumping Rates
- Appendix A.4: CCWF and Chino II Expansion Wells PDR (GEOSCIENCE, 2009)

APPENDIX B: WELL PUMPS

- Appendix B.1: Southern California Edison (SCE) Tests of CDA Wells
- Appendix B.2: [Not Used]
- Appendix B.3: [Not Used]
- Appendix B.4: Chino II Raw Water System Hydraulic Calculations

APPENDIX C: WATER QUALITY

- Appendix C.1: Chino I Well VOC Data
- Appendix C.2: CCWF 10-Year Travel Time Water Quality

APPENDIX D: DESALTERS

- Appendix D.1: Chino I Hydraulic Grade Line, Etc.
- Appendix D.2: Chino I Desalter Product Water Pump Station Criteria
- Appendix D.3: Chino II Expansion Criteria
- Appendix D.4: Chino II Expansion Supplemental Spare Parts

APPENDIX E: CONCENTRATE

- Appendix E.1: Chino II Sari Direct User Discharge Permit
- Appendix E.2: SARI Purchase Agreements for Chino I and Chino II
- Appendix E.3: Pellet Marketing Survey

APPENDIX F: PRODUCT WATER

- Appendix F.1: Chino II Expansion Product Water Delivery Facilities Technical Memorandum
- Appendix F.2: Pipeline Design Criteria
- Appendix F.3: Plan and Profile of Proposed Riverside-Hamner Pipeline
- Appendix F.4: Hamner Pipeline Drawings
 - Schliesman Rd to South of Santa Ana River (Design Drawings): Sheets 5-10
 - South of Santa Ana River to West Side of Detroit Street Bridge (Record Drawings): Sheets 11-12, 13A
 - Detroit Street Bridge (Design Drawing): Sheet 13B
- Appendix F.5: Chino II 1010 Zone Product Water Pump Station Hydraulic Grade Line Calculations
- Appendix F.6: [Not Used]

Appendix F.7: Milliken Pump Station MWH Technical Memorandum

APPENDIX G: COSTS

Appendix G.1: Buy-In Methodology

Appendix G.2: Well Cost Estimates

Appendix G.3: Raw Water Pipeline Cost Estimates

Appendix G.4: Raw Water Pump Station Cost Estimates

Appendix G.5: Treatment Plant Cost Estimates

Appendix G.6: Product Water Pipeline Cost Estimates

Appendix G.7: Product Water Pump Stations Cost Estimates

Appendix G.8: Concentrate Disposal Pipeline

Appendix G.9: Desalter Expansion Option A and Option B Costs

Appendix G.10: Independent O&M Cost Review

APPENDIX H: COMMENTS

LIST OF TABLES

Table 1.1	Volumes and Capacities	1-3
Table 1.2	CDA Product Water Entitlement	1-4
Table 2.1	Summary of Existing Chino Desalter Well Equipment ^a	2-4
Table 2.2	Summary of Groundwater Model Well Production Rates	2-11
Table 2.3	Current and Projected Conditions for Pump Setting and Screens	2-14
Table 3.1	Extremely Impaired Well Treatment Cost Comparison	3-13
Table 4.1	Summary of Chino I VOC Levels	4-7
Table 4.2	Summary of Chino I TCP Treatment Options	4-17
Table 4.3	Water Quality and Treatment Process Alternatives	4-19
Table 4.4	Chino I Product Water Nitrate and TDS Levels	4-22
Table 4.5	Chino II Product Water Nitrate and TDS Levels	4-33
Table 4.6	Chino II Expansion Criteria Summary	4-36
Table 5.1	SARI Ownership (2006)	5-2
Table 5.2	Chino I SARI Capacity Requirements	5-4
Table 5.3	Chino II SARI Capacity Requirements	5-5
Table 5.4	Effect of Concentrate Reduction on Flows and Efficiencies	5-10
Table 5.5	Concentrate Reduction Chemical Delivery Schedule	5-16
Table 5.6	Concentrate Reduction Labor Requirements	5-17
Table 5.7	Chino Desalter Concentrate Reduction Operation and Maintenance Cost Estimates	5-18
Table 5.8	Chino Desalter Concentrate Reduction Capital Cost Estimate	5-19
Table 5.9	Effect of Concentrate Reduction on SARI Capacity Costs	5-20
Table 5.10	Concentrate Reduction Annual Cost Comparison	5-23
Table 6.1	Chino II Product Water Pumping Requirements: 20.5 mgd Capacity	6-4
Table 6.2	Chino II Product Water Pumping Requirements: 22.7 mgd Capacity	6-5
Table 6.3	Summary of Chino II Pressure Zone Pumping Costs	6-8
Table 6.4	Summary of Pipeline Design Criteria ^a	6-12
Table 6.5	Comparison of Hamner Avenue Pipe Diameter Options Between Riverside Dr. and Schleisman Rd. ^a	6-15
Table 6.6	Summary of Existing CDA Product Water Pump Station	6-17
Table 6.7	Chino II Product Water Pump Station Criteria	6-18
Table 6.8	Milliken Pump Station Criteria	6-22
Table 7.1	Summary of Permit Information	7-9
Table 8.1	Historical SARI Treatment and Pipeline Capacity Costs	8-2
Table 8.2	Summary of SARI Capital Costs	8-3
Table 8.3	Current SARI Volumetric and Use Charges	8-4
Table 8.4	Summary of Phase 3 Project Options Capital Costs	8-9
Table 8.5	Summary of Phase 3 Options Capacities	8-10
Table 8.6	Summary of Construction Project Capital Costs for Option C: Expand Chino II to 22.7 mgd with Concentrate Reduction	8-12
Table 8.7	Raw Water Pumping Costs	8-13
Table 8.8	Summary of O&M Costs for Option C (Expand Chino II to 22.7 mgd with Concentrate Reduction)	8-16
Table 8.9	Grant Funding	8-17
Table 8.10	Capital Cost Distribution for Option C (Expand Chino II to 22.7 mgd with Concentrate Reduction)	8-19
Table 8.11	Current and New CDA Costs (FY 09/10 Budget Year) for Option C (Expand Chino II to 22.7 mgd with Concentrate Reduction)	8-21
Table 8.12	Summary of Unit Costs (Includes O&M and Debt Services)	8-22

LIST OF FIGURES

Figure 2.1	Groundwater Elevation Contours and Flow.....	2-3
Figure 2.2	GEOSCIENCE Scenario 1 Model Groundwater Level Changes	2-6
Figure 2.3	GEOSCIENCE Scenario 2 Model Groundwater Level Changes	2-7
Figure 2.4	GEOSCIENCE Scenario 3 Model Groundwater Level Changes	2-8
Figure 2.5	Chino Desalter Well Locations	2-10
Figure 3.1	Vicinity Map.....	3-2
Figure 3.2	Chino Desalter Raw Water Intertie Options	3-4
Figure 3.3	Chino Desalter Raw Water Intertie Schematic.....	3-6
Figure 3.4	Raw Water Intertie Site Plan.....	3-7
Figure 3.5	Chino II Raw Water Pipeline Plan	3-9
Figure 3.6	Chino II Raw Water Pipeline Profile	3-10
Figure 4.1	Chino Desalter Well Field Nitrate Levels.....	4-4
Figure 4.2	Chino Desalter Well Field TDS Levels	4-5
Figure 4.3a	Current and Projected VOC Plume Locations.....	4-9
Figure 4.3b	VOC Pie Chart Comparison Map.....	4-10
Figure 4.4	Short-Term Modeled and Historical Raw Water TCP Levels.....	4-12
Figure 4.5	Projected TCP Concentrations in Existing Chino I Desalter Wells	4-13
Figure 4.6	Projected TCP Concentrations in Chino Creek Well Field A	4-14
Figure 4.7	Historical and Projected Chino I Product Water TCP Concentrations	4-16
Figure 4.8	Chino I Process Flow Frequency Distributions.....	4-21
Figure 4.9	Effect of Raw Water TDS on Existing Chino I Capacity.....	4-23
Figure 4.10	Frequency Distribution of Chino I RO/IX Raw Water TDS.....	4-25
Figure 4.11	Effect of Raw Water TDS on Chino I Capacity with Additional RO.....	4-27
Figure 4.12	Effect of Raw Water TDS on Chino I Capacity with VOC Air Stripper Supply Wells at 1.5 mgd	4-29
Figure 4.13	Chino II Process Flow Frequency Distributions.....	4-32
Figure 4.14	Effect of Raw Water TDS on Expanded Chino II Bypass	4-34
Figure 5.1	Chino I SARI Flow Frequency Distribution	5-3
Figure 5.2	Chino II SARI Flow Frequency Distribution	5-7
Figure 5.3	Chino Desalter Concentrate Reduction Schematic.....	5-11
Figure 5.4	Chino I Concentrate Reduction Site Plan.....	5-14
Figure 5.5	Chino II Concentrate Reduction Site Plan.....	5-15
Figure 5.6	Effect of Pellet Disposal Cost on Concentrate Disposal Cost.....	5-24
Figure 6.1	Overview of Option A Product Water Delivery Facilities	6-6
Figure 6.2	Chino II Product Water Pumping Schematic.....	6-7
Figure 6.3	Overview of WMWD Delivery Facilities	6-10
Figure 6.4	Overview of Riverside-Hamner Product Water Pipeline	6-14
Figure 6.5	Chino II Product Water Pump Station Site Plan.....	6-20
Figure 6.6	Chino II 1010 Zone Pump Station System Curves.....	6-21
Figure 6.7	Milliken Pump Station Site Plan.....	6-23